


A vertical list of 15 geometric shapes, each separated by a horizontal line. The shapes are: a rectangle with a small octagon on its right side; a rectangle with a small octagon on its right side and a diagonal line from the top-left corner to the octagon; a rectangle with a diagonal line from the top-left corner to the right side; a rectangle with a vertical line from the top edge to the center; a rectangle with a diagonal line from the top-left corner to the bottom-right corner; a rectangle with a small octagon on its right side and a diagonal line from the top-left corner to the octagon; a rectangle with a small octagon on its right side; a rectangle with a small octagon on its right side and a diagonal line from the top-left corner to the octagon; a rectangle with a small octagon on its right side; a rectangle with a small octagon on its right side and a diagonal line from the top-left corner to the octagon; a rectangle with a small octagon on its right side; a rectangle with a small octagon on its right side and a diagonal line from the top-left corner to the octagon; a rectangle with a small octagon on its right side; a rectangle with a small octagon on its right side and a diagonal line from the top-left corner to the octagon; a rectangle with a small octagon on its right side.



D2	
Papa termozgrzewalna	0,5 cm
Papa podkładowa	0,5 cm
Szlichta spadkowa (5-10cm)	7,0 cm
Styropian EPS100	25,0 cm
Paroizolacja	0,1 cm
Strop	24,0 cm
Suma	59,1 cm

<b>S3</b>	
Wykładzina PCV	0,5 cm
Szlichta	7,0 cm
Styropian EPS-100	7,0 cm
Izolacja przeciw wodna	0,5 cm
Strop	24,0 cm
Styropian EPS70	15,0 cm
Tynk	0,5 cm
Suma	54,5 cm

TEMA	ODDZIAŁU GERIATRII I REHABILITACJI			
	Parcowa 4, Koszalin 136			
OPIS	PŁY WENTYLACJI MECHANICZNEJ PRZEBUD. X-X- REHABILITACJI			
PROJEKTANT	NR DOK. PROJEKTU	DATA		NR KRS
ING. H.Z. J. JÓZEFOWICZ	BR. 77/763	15.02.2019r.		12
BERAZA	SKALA	1:50		